

Fit-out breakdown and revised forecast

Rebuilt on a building in good shape.

01 / THE REVISED BASIS

What changed, and what it is worth.

The NGN 370M fit-out in the commercial model assumed a full conversion: strip out, full rewire, structural and roof repairs, new ceilings throughout. On the steer that the property is sound and needs interior decoration and some partitioning at most, the whole forecast rebuilds. Three cases are carried through this note.

NGN M unless stated	Full conversion	Realistic	Lean
Building fit-out element	241	148	121
Per sqm across 711 sqm gross	339,000	208,000	170,000
PropCo fit-out, all in	370	232	183

Plan on the realistic case. It takes roughly NGN 138M off the fit-out against a full conversion, and the lean case is what you fall back to if the head lease cannot be extended beyond two years. This note covers the fit-out only. Capital, cost base, payback and the five-year outlook are in the companion engagement note, which carries the Mezo management fee and the current space plan.

02 / THE BREAKDOWN

Package by package.

A. Building fit-out

Package	Full	Realistic	Lean
Cooling: about 28 split units, ceiling cassettes front of house	34	24	22
ICT: cabling, network, CCTV, access control, emergency call, room-status displays	17	15	14
Electrical: distribution boards, solar and grid load zoning, medical circuits, emergency lighting	30	14	12
Joinery: reception desk, nurse stations, room casework, storage	21	14	11
Interior decoration: painting, window treatments, soft finishes	17	12	10
Fire: detection, alarm, escape lighting, extinguishers	14	9	8
Clinical flooring: welded and coved vinyl, clinical areas only	23	9	4
Ceilings and lighting	19	9	6
Partitioning: subdivide two living rooms, no wall removal	in enabling	8	8
Procedure room: scrub and clinical services	9	7	6
Signage and wayfinding	in painting	7	4
Mechanical fresh air and extract	7	6	5
Plumbing: clinical hand-wash points, condensate runs	11	6	5
Doors and ironmongery	13	5	3
Medical waste holding and route	4	3	3
Enabling: strip out, structural and roof repairs	22	nil	nil
Building fit-out	241	148	121

Per sqm across 711 sqm gross: **NGN 339,000** full, **NGN 208,000** realistic, **NGN 170,000** lean. A light-touch clinical conversion in Nigeria sits at NGN 180,000 to NGN 250,000 per sqm, so the realistic case lands mid-range and the lean case is at the floor of what is deliverable.

B. Everything else

Package	Full	Realistic	Lean
Building fit-out, from A	241	148	121
FF&E;: 8 consulting rooms, FUE suite, procedure, reception, waiting, lounge	32	30	26
External: car park, lighting, drainage, gate house, perimeter	26	10	6
Water: treatment, storage, pressure, hot water	10	5	3
Design, M&E; consultant, project management, approvals	22	14	10
Contingency	40 at 12%	25 at 12%	17 at 10%
PropCo fit-out total	370	232	183

C. Also Medbury cash, different entities

Package	Full	Realistic	Lean
Medbury Diagnostics unit: benching, safety cabinets, reagent cold chain, specimen reception	34	28	24
Medbury Pharmaceuticals unit: dispensing counter, controlled drugs store, shelving, cold chain	29	24	20
Total Medbury fit-out cash	433	284	227

Not Medbury's cash. Radiology shielding, room and equipment sit under Medbury Diagnostics' arrangement with the imaging partner. Medlyfe funds its own guest chalet clinical fit-out at roughly NGN 35M. The 25KVA hybrid power system is a separate NGN 33M line and is not inside any figure above.

03 / WHAT DOES NOT REDUCE

Good building condition helps less than it looks.

Six packages are driven by the change of use, not by the state of the building. They total **NGN 75M in the realistic case, half the building fit-out**, and they would be the same in a brand new house.

Package	NGN M	Why building condition is irrelevant
Cooling	24	A four-bedroom house has six to eight units. A campus needs about 28
ICT	15	Access control, CCTV, emergency call and clinical-grade cabling do not exist in a house
Fire	9	Detection, alarm and escape lighting to commercial standard
Partitioning	8	Bedrooms and living rooms are not consulting rooms
Fresh air	6	Split units recirculate. Clinical spaces need mechanical ventilation
Medical waste	3	A compliant holding area and route, outside clinical space
	75	

No nurse call system. Nurse call is inpatient infrastructure: bedside bells, corridor domes and a central annunciator, for patients who are in a bed and cannot walk. This is an ambulatory centre where every patient is either with a clinician or in a waiting area, so the spec is wrong for the building. What replaces it is a hardwired **emergency call button in each clinical room and an emergency pull cord in every WC**, which is a safety floor and probably a licensing requirement, plus **room-status displays**. Everything else that a nurse call system would have done, chaperone requests, specimen collection, next-patient calls and room turnaround, belongs in the EMR or the staff app. The roughly NGN 3M saved on hardware is reallocated to the emergency call circuit and the room-status displays rather than taken out, so the ICT line is unchanged.

The electrical line is the one to watch. I have cut it from NGN 30M to NGN 14M on the assumption that existing wiring is serviceable. But a residential incoming supply and distribution board will not carry 28 air conditioning units plus imaging plus a laboratory. The incoming capacity, the main board and the load zoning for solar all need upgrading whatever condition the wiring is in. If the supply turns out to be undersized, this line goes back toward NGN 30M on its own.

04 / WHERE IT LANDS

How the fit-out sits in the capital plan.

Under the current space plan, Medbury Diagnostics and Medbury Pharmaceuticals occupy the guest chalet and the boys' quarters, so the fit-out splits three ways by who funds it. The package rates in section 02 are the method; these are the totals they produce.

Funded by	NGN M
PropCo: the main building, 563 sqm gross	208
Medbury Diagnostics: chalet conversion, laboratory, and the imaging suite in the main building	75
Medbury Pharmaceuticals: boys' quarters conversion and dispensary	38
Total Medbury fit-out cash	321

Converting two outbuildings costs more than fitting the same functions inside the main house, which is why the diagnostics and pharmacy lines are higher than they were when both sat on the ground floor. It is the right trade: it frees the ground floor for the Conversion Clinic and it puts the laboratory and the dispensary where they belong, out of the patient route.

05 / CONDITIONS

What would move the fit-out number.

Risk	Effect	Note
Incoming electrical supply undersized	+NGN 16M	The single most likely overrun. A residential supply will not carry 28 AC units, imaging and a laboratory
Structure found on opening walls for partitioning	+NGN 10 to 22M	The enabling package returns. Cannot be known until walls are opened
Roof condition, before the rains	+NGN 8 to 15M	Not visible from a walk-through. Worth a specific inspection
No functioning borehole or storage	+NGN 8M	The water line assumes existing infrastructure is serviceable
Ceilings not sound	+NGN 10M	Ceilings and lighting was cut from 19 to 9 on the assumption they stay

The head lease condition still holds. A lower fit-out softens it but does not remove it. NGN 321M amortised over two years is NGN 161M a year against a campus that produces NGN 282M of revenue in year one. Over a five plus five it is NGN 32M. Five plus five remains the condition before capital is released, and at this level of spend the case for phasing largely disappears: doing it in one pass avoids returning contractors to a trading clinical building.

Before this is used to commit capital

What	Why
A quantity surveyor's take-off	This is still the largest line in the project and the least verified. Every figure here is built up by package, not measured
An electrical load assessment	Incoming supply capacity and main board rating against a 38kW average and 55kW peak
A condition survey	Roof, ceilings, wiring age, borehole and storage. Confirms or removes the assumptions this note rests on
Confirmation of the areas	Measured from the as-built PDFs at about 711 sqm gross. Every per sqm figure re-bases if the CAD differs

Debo Odulana Consult for Africa / +234 913 813 8553 / hello@consultforafrica.com

Fit-out figures are built up by package at Nigerian clinical rates and are estimates, not a take-off. The realistic case rests on the steer that the building is structurally sound and needs decoration and partitioning at most, which a condition survey should confirm. Not a binding offer, and not legal or tax advice. FX USD/NGN 1,550.